Sl. No	Description of Work	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
5	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per directions of the Engineer-in-charge. Specification No. KBS 4.6.3(Item no: 4.46.2, Page no: 17 of KPWD S.R 2015-16).								
	For Drain	T	5.88			5.88		
						Total Qty	**5.88**	**69805.80**	**410623.12**
6	Providing and laying pre-cast drain cover slab of 100mm thickness in CM1:3 including cost of all materials,labour,curing, transportation, loading, unloading etc.,as per doiirections of the Enineer-in-charge. {Data Rate sheet enclosed}								
	CC Drain	Sqm	1	30.00	0.70		21.00		
						Total Qty	**21.00**	**1821.00**	**38241.00**
7	KSRB 6-7.3 : Construction of partition wall 11.2 cms thick with non- modular ground moulded burnt bricks of class designation 3.5 Newton per sqmm with cement mortar 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2(P.No.28, I.No.6.25 of PW, P&IWTD S.R 2015-16).								
	Brick wall	Sqm	1	20.00		2.50	50.00		
						Total Qty	**50.00**	**824.04**	**41202.00**
8	KSRB15-5.1 : Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4, to brick masonry for base of dadooing works with sand of approved quality, providing and removingscaffolding, including cost of materials labour,curing complete as per specifications.								
	Brick wall	Sqm	1	20.00		5.50	110.00		
						Total Qty	**110.00**	**181.44**	**19958.40**
9								**Total construction cost**	**19,57,894.92**
10								**Design Report,Proof Checking & PMC Amount**	**39,157.90**
11								**Sub Total**	**19,97,052.82**
12								**Miscellaneous & Rounding Off**	**2,947.18**
								Grand Total	**20,00,000.0**

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2015-16
4. The provisions made in the estimate are necessary and essential.

Consultants
For Sri Sai Consultants

Assistant Engineer
Ward No-15
BBMP - Bangalore

Assistant Executive Engineer
Dasarahalli-Sub division
BBMP - Bangalore

Executive Engineer
Dasarahalli
BBMP - Bangalore

ನಂ.CE/DZ/AS/107/15-16 ದಿನಾಂಕ : 25-1-16
ರೂ.20,00,000 (ಇಪ್ಪತ್ತು ಲಕ್ಷ ರೂಪಾಯಿಗೆ)
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ. EE/DD/15/83/15-16 ದಿನಾಂಕ : 25.1.2016
ರೂ.20.00 ಲಕ್ಷಗಳು (ರೂ. ಇಪ್ಪತ್ತು ಲಕ್ಷಗಳು ಮಾತ್ರ)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
P-18/83
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Sl. No	Description of Work	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
8	KSRRB M600-2. Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 25mm and down size graded granite metal coarse aggregate with superplastisizer at 3lts conforming to IS 9103-1999 reaffirmed 2008, (Coarse and fine aggregate conforming to IS: 383) mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver,spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane,sealant primer, joint sealant, debonding strip, dowel bar, tie rod, ,admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications MORTH Specification No. 602- with M30 @ 360 Kg/cum Cement, C.A, 0.69 cum F.A. 0.46 cum.(Page No.-173 I.No-22.2.1 of KPWD S.R 2015-16).								
	Mazidi Roads								
	Ch:00-191	Cum	1	191.00	3.50	0.15	100.28		
	Ch:00-100 Mazidi parallel Road		1	100.00	2.70	0.15	40.50		
	Ch:100-170		1	70.00	3.40	0.15	35.70		
	Ch:170-192		1	22.00	2.70	0.15	8.91		
	model colony								
	Ch:00-80 adjusent compound rd		1	80.00	5.80	0.15	69.60		
	Ch:00-95 1st main		1	95.00	7.00	0.15	99.75		
	Ch:00-78 1 st and 2nd Cross		1	122.00	4.20	0.15	76.86		
						Total Qty	431.60	6943.32	2996702.20
9								Total construction cost	41,10,088.04
10								Design Report,Proof Checking & PMC Amount	82,201.76
11								Sub Total	41,92,289.80
								Miscellaneous & Rounding Off	7,710.20
								Grand Total	42,00,000.0

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2ar 2015-16
4. The provisions made in the estimate are necessary and essential.

SRI SAI CONSULTANTS BANGALORE-90

Consultants
For Sri Sai Consultants

Assistant Engineer
Ward No.-15
BBMP - Bangalore

Assistant Executive Engineer
Dasarahalli Sub-Division
BBMP - Bangalore

Executive Engineer
Dasarahalli
BBMP - Bangalore

ನಂ. CE/DZ/AS/No1/15-16 ದಿನಾಂಕ: 25.1.16
₹ 42,00,000 (ನಲವತ್ತ ಎರಡು ಲಕ್ಷ ರೂಗಳಿಗೆ) ಗಳ
ಷ ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಮುಖ್ಯ ಅಭಿ
ದಾಸರಹಳ್ಳಿ

94
CE/DZ/TS/ /15-16 ದಿನಾಂಕ 25.1.16
42,00,000 (ನಲವತ್ತ ಎರಡು ಲಕ್ಷ ರೂಗಳಿಗೆ)
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Sl No	Description of Work	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
5	KSRRB M600-2. Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 25mm and down size graded granite metal coarse aggregate with superplastisizer at 3lts conforming to IS 9103-1999 reaffirmed 2008, (Coarse and fine aggregate conforming to IS: 383) mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver,spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane,sealant primer, joint sealant, debonding strip, dowel bar, tie rod, ,admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications MORTH Specification No. 602- with M30 @ 360 Kg/cum Cement, C.A, 0.69 cum F.A. 0.46 cum.(Page No.-173 I.No-22.2.1 of KPWD S.R 2015-16).								
	maheshwari nagar								
	Ch:00-100	Cum	1	100.00	3.50	0.15	52.50		
	Ch:100-158		1	58.00	3.90	0.15	33.93		
	Ch:158-218		1	60.00	4.30	0.15	38.70		
	Ch:218-271		1	53.00	3.90	0.15	31.01		
	Ch:271-381 1st Cross Roads		1	110.00	4.00	0.15	66.00		
	Ch:381- 456 2nd Cross Roads		1	75.00	4.45	0.15	50.06		
						Total Qty	272.20	6943.32	1889954.35
6							Total construction cost		24,50,636.76
7							Design Report,Proof Checking & PMC Amount		36,759.55
8							Sub Total		24,87,396.31
9							Miscellaneous & Rounding Off		12,603.69
10							Grand Total		25,00,000.0

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circlear 2015-
4. The provisions made in the estimate are necessary and essential.

SRI SAI CONSULTANTS BANGALORE-90

Consultants
For Sri Sai Consultants

Assistant Engineer
Ward No.-15
BBMP - Bangalore

Assistant Executive Engineer
Dasarahalli Sub-Division
BBMP - Bangalore

Executive Engineer
Dasarahalli
BBMP - Bangalore

102
ನಂ. CE/D2/AS/ /ದಿನಾಂಕ: 25.1.2016
ರೂ. 25,00,000 (ಇಪ್ಪತ್ತೈದು ಲಕ್ಷ ಮಾತ್ರ)
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

95
ನಂ. CE/D2/TS/ /ದಿನಾಂಕ: 25-1-16
ರೂ. 25,00,000 (ಇಪ್ಪತ್ತೈದು ಲಕ್ಷ ಮಾತ್ರ)
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾ
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು
ಬಿ.ಬಿ.ಎ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Sl. No	Description of Work	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
7	KSRRB M600-2. Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 25mm and down size graded granite metal coarse aggregate with superplastisizer at 3lts conforming to IS 9103-1999 reaffirmed 2008, (Coarse and fine aggregate conforming to IS: 383) mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver,spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane,sealant primer, joint sealant, debonding strip, dowel bar, tie rod, ,admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications MORTH Specification No. 602- with M30 @ 360 Kg/cum Cement, C.A, 0.69 cum F.A.								
	officers model colony								
	Ch:00:115	Cum	1	115.00	4.80	0.15	82.80		
	Ch115-189		1	74.00	6.00	0.15	66.60		
	Ch:189-262		1	73.00	4.30	0.15	47.09		
	Ch:262-333		1	71.00	3.20	0.15	34.08		
	Ch:333-358		1	25.00	3.50	0.15	13.13		
	Ch:358-380 3rd Cross		1	22.00	4.60	0.15	15.18		
						Total Qty	258.87	6943.32	1797417.25
								Total construction cost	24,46,030.45
8								Design Report,Proof Checking & PMC Amount	48,920.61
9								Sub Total	24,94,951.06
10								Miscellaneous & Rounding Off	5,048.94
								Grand Total	25,00,000.0

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2014-15
4. The provisions made in the estimate are necessary and essential.

SRI SAI CONSULTANTS BANGALORE-90

Consultants
For Sri Sai Consultants

Assistant Engineer
Ward No.-15
BBMP - Bangalore

Assistant Executive Engineer
Dasarahalli Sub-Division
BBMP - Bangalore

Executive Engineer
Dasarahalli
BBMP - Bangalore

104

ನಂ.CE/DZ/AS/ /ದಿನಾಂಕ: 25-1-16

ರೂ.25,00,000 (ಇಪ್ಪತ್ತೈದು ಲಕ್ಷ ರೂಗಳಿಗೆ)

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಮುಖ್ಯ ಅಭಿಯಂತರರು

ಬಿ.ಬಿ.

ದಾಸರಹಳ್ಳಿ

96

ನಂ.CE/DZ/TS/ /ದಿನಾಂಕ: 25-1-16

25,00,000 (ಇಪ್ಪತ್ತೈದು ಲಕ್ಷ ರೂಗಳಿಗೆ)

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂ

ಮುಖ್ಯ ಅಭಿ

ನಾಯಕರು ಬಿ.ಬಿ.

ದಾಸರಹಳ್ಳಿ ವಲಯ

Sl.	Description of Work	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
8	Providing, laying, spreading and compacting graded stone aggreate to wet mix mecadam specification including premixing the materials with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achive the desired density complete as per specifications. (Page No,-154, I.No.-20.18 of KPWD S.R 2015-16).								
	Standard School Front Road	Cum							
	Ch:00-36		1	15.00	3.05	0.15	6.86		
						Total Qty	6.86	1713.96	11762.05
9	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No. KBS 4.1,4.2 (Page No. 12, It No. 4.2 of KPWD S.R 2015-16)								
	Maszide Road								
	Ch:00-44 For Drain		2	44.00	0.90	0.15	13.20		
	Maszide Road	Cum							
	Ch:00-44		1	44.00	3.35	0.15	22.11		
	Standard School Back Side Road								
	Ch:00-198		1	25.00	4.40	0.15	16.50		
	Standard School Front Side Road								
	Ch:00-36		1	30.00	3.05	0.15	13.73		
						Total Qty	65.54	5236.92	343201.55
10	KSRRB M600-2. Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 25mm and down size graded granite metal coarse aggregate with superplastisizer at 3lts conforming to IS 9103-1999 reaffirmed 2008, (Coarse and fine aggregate conforming to IS: 383) mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver,spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane,sealant primer, joint sealant, debonding strip, dowel bar, tie rod, ,admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications MORTH Specification No. 602- with M30 @ 360 Kg/cum Cement, C.A, 0.69 cum F.A. 0.46 cum.(Page No.-173 I.No-22.2.1 of KPWD S.R 2015-16).)								
	Maszide Road Near std School	Cum							
	Ch:00-44		1	44.00	3.35	0.15	22.11		
	Standard School Back Side Road								
	Ch:00-198		1	198.00	4.40	0.15	130.68		
	Standard School Front Side Road								
	Ch:00-36		1	36.00	3.05	0.15	16.47		
	Ch:36-157		1	121.00	2.40	0.15	43.56		
						Total Qty	212.82	6943.32	1477677.36
11								Total Construtions cost	29,22,986.37
12								Design Report,Proof Checking & PMC Amount	73,074.66
13								Sub Total	29,96,061.03
14								Miscellaneous & Rounding Off	3,938.97
								Grand Total	30,00,000.00

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2015-16.
4. The provisions made in the estimate are necessary and essential.

SRI SAI CONSULTANTS BANGALORE-90

Consultants
For Sri Sai Consultants

ನಂ CE/DZ/AS/105/15-16 ದಿನಾಂಕ: 25.1.16
ರೂ 30,00,000 (ಮೂವತ್ತು ಲಕ್ಷ ರೂಪಾಯಿಗಳಿಗೆ)
ಮೇಲಿನಂತೆ ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀ.
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬ

Assistant Engineer
Ward No-15
BBMP - Bangalore

Assistant Executive Engineer
Dasrahalli-Sub division
BBMP - Bangalore

Executive Engineer
Dasrahalli
BBMP - Bangalore

Sl. No	Description of Work	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
11	KSRRB M600-2. Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 25mm and down size graded granite metal coarse aggregate with superplastisizer at 3lts conforming to IS 9103-1999 reaffirmed 2008, (Coarse and fine aggregate conforming to IS: 383) mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver,spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane,sealant primer, joint sealant, debonding strip, dowel bar, tie rod, ,admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications MORTH Specification No. 602- with M30 @ 360 Kg/cum Cement, C.A, 0.69 cum F.A. 0.46 cum.(Page No.-173 I.No-22.2.1 of KPWD S.R 2015-16).								
	Kalahasthi nagar								
	Ch:00-182 4th cross and Cro roads	Cum	2	91.00	4.00	0.15	109.20		
	Ch:182-227		1	45.00	4.00	0.15	27.00		
	Ch:227-317 Cross Roads		1	90.00	2.80	0.15	37.80		
	Ch:317-447 5th Cross Roads		1	130.00	4.00	0.15	78.00		
	Ch:447-567 6th cross roads		1	120.00	4.50	0.15	81.00		
	Ch:00-20		1	72.00	4.00	0.15	43.20		
						Total Qty	**376.20**	**6943.32**	**2612076.98**
12								**Total Constrution cost**	**41,12,248.90**
13								**Design Report,Proof Checking & PMC Amount**	**82,244.98**
14								**Sub Total**	**41,94,493.88**
								Miscellaneous & Rounding Off	**5,506.12**
								Grand Total	**42,00,000.00**

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2015-16
4. The provisions made in the estimate are necessary and essential.

SRI SAI CONSULTANTS ★ BANGALORE-90 ★

Consultants
For Sri Sai Consultants

Assistant Engineer
Ward No.15
BBMP - Bangalore

Assistant Executive Engineer
Dasarshalli Sub-Division
BBMP - Bangalore

Executive Engineer
Dasarshalli
BBMP - Bangalore

103
ನಂ. CE/DZ/AS/ /15-16 ದಿನಾಂಕ: 25-1-2016.
ರೂ. 42,00,000 (ನಲವತ್ತ ಎರಡು ಲಕ್ಷ ರೂಗಳಿಗೆ
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿ
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ದಾಸರಹಳ್ಳಿ

97
ನಂ. CE/DZ/TS/ /15-16 ದಿನಾಂಕ: 25.1.16
ರೂ. 42,00,000 (ನಲವತ್ತ ಎರಡು ಲಕ್ಷ ರೂಗಳಿಗೆ
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Sl. No	Description of Work	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
10	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface - Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sq.m. area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC :35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. (Page No,-181, I.No.-24.15 of KPWD S.R 2015-16).								
	Edge Lane	Sqm	2	540.00	0.15		162.00		
						Total Qty	**162.00**	**473.04**	**76632.48**
11								**Total Constrution cost**	**40,88,281.14**
12								**Design Report,Proof Checking & PMC Amount**	**1,02,207.03**
13								**Sub Total**	**41,90,488.17**
14								**Miscellaneous & Rounding Off**	**9,511.83**
								Grand Total	**42,00,000.00**

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2015-16
4. The provisions made in the estimate are necessary and essential.

SRI SAI CONSULTANTS

Consultants
For Sri Sai Consultants

Assistant Engineer
Ward No-15
BBMP - Bangalore

Assistant Executive Engineer
Dasrahalli-Sub division
BBMP - Bangalore

Executive Engineer
Dasrahalli
BBMP - Bangalore

108

ನಂ.CE/DZ/AS/ /ದಿನಾಂಕ:25.1.16
ರೂ.42,00,000 (ನಲವತ್ತೆ ಎರಡು ಲಕ್ಷ ರೂಗಳಿಗೆ)
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡ...
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ
ದಾಸರಹಳ್ಳಿ ವಲಯ

99

ನಂ.CE/DZ/TS/ /ದಿನಾಂಕ:25.1.16
ರೂ.42,00,000 (ನಲವತ್ತೆ ಎರಡು ಲಕ್ಷ ರೂಗಳಿಗೆ)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾ...
ಮಂಜೂರಾತಿ ನೀಡಲಾಗಿದೆ.
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು ಬಿ.ಬಿ.ಎಂ.ಪಿ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Sl No	Description of Work	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
9	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VGIO) on the prepared black topped surfaces at 2.5 kg per 10sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.MORTH Chapter 5 (Page No,160,I.No.-21.7 of KPWD S.R 2015-16)								
	Kempegegowda Layuot Main Rd								
	Ch:00-130	Sqm	1	130.00	7.00		910.00		
	Ch:130-255		1	125.00	6.00		750.00		
	Pipe line Cutting		20	6.00	0.60		72.00		
						Total Qty	1732.00	15.12	26187.84
10	KSRRB M500-19. Providing and laying bituminous concrete 40 mm thick with hot mix plant, using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 6 % VG-30 Bitumen using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. MORTH Specification No. 509.(Page No-164 Item no - 21.22.6 of KPWD SR 2015-16)..								
	Kempegegowda Layuot Main Rd								
	Ch:00-130	Cum	1	130.00	7.00	0.04	36.40		
	Ch:130-255		1	125.00	6.00	0.04	30.00		
	Pipe line Cutting		20	6.00	0.60	0.04	2.88		
						Total Qty	69.28	9901.17	685953.06
11	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface - Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sq.m. area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC :35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. (Page No,-181, I.No.-24.15 of KPWD S.R 2015-16).								
	Edge Lane	Sqm	2	255.00	0.15		76.50		
						Total Qty	76.50	473.04	36187.56
12								Total Constrution cost	9,78,782.14
13								Design Report,Proof Checking & PMC Amount	19,575.64
14								Sub Total	9,98,357.78
								Miscellaneous & Rounding Off	1,642.22
								Grand Total	10,00,000.00

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2015-16
4. The provisions made in the estimate are necessary and essential.

EE/DD/Rs/84/15-16, dt: 25/1/16

ರೂ. 10.00 ಲಕ್ಷಗಳು (ರೂ. ಹತ್ತು ಲಕ್ಷಗಳು ಮಾತ್ರ)

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

P-18/84

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

109

AE/DZ/AS/ 15-16 ದಿನಾಂಕ: 25.1.16

ರೂ. 10,00,000 (ಹತ್ತು ಲಕ್ಷ ರೂಗಳಿಗೆ)

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ವಲಯ

Consultants
For Sri Sai Consultants

Assistant Engineer
Ward No.-15
BBMP - Bangalore

Assistant Executive Engineer
Dasarahalli Sub-Division
BBMP - Bangalore

Executive Engineer
Dasarahalli
BBMP - Bangalore

Sl. No	Description of Work	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
10	KSRRB 500-7. Providing and applying tack coat on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.MORTH /Chapter 5 (Page No160,-, I.No.-21.7 of KPWD S.R 2015-16).								
	Ch:00-116 2nd Main Road	Sqm	1	116.00	4.50		522.00		
	Ch:116-156 1st Cross Road		1	40.00	4.60		184.00		
	Ch:156-196 2nd Cross Road		1	40.00	6.00		240.00		
	Bwssb cutting along road		1	300.00	0.80		240.00		
						Total Qty	**1186.00**	**15.12**	**17932.32**
11	KSRRB M500-17. Providing and laying dense graded bituminous macadam using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications. (Page No,-162, I.No.-21.17.6 of KPWD S.R 2015-16).								
	Ch:00-150 1st Main Approch Road	Cum	1	65.00	7.0	0.05	22.75		
						Total Qty	**22.75**	**8005.77**	**182131.27**
12	KSRRB M500-19. Providing and laying bituminous concrete 40 mm thick with hot mix plant, using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 6 % VG-30 Bitumen using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. MORTH Specification No. 509.(Page No-164 Item no - 21.22.6 of KPWD SR 2015-16)..								
	For Laying BC	Cum							
	Ch:00-116 2nd Main Road		1	116.00	4.50	0.04	20.88		
	Ch:116-156 1st Cross Road		1	40.00	4.60	0.04	7.36		
	Ch:156-196 2nd Cross Road		1	40.00	6.00	0.04	9.60		
	Ch:196-346 1st Main Road		1	150.00	6.30	0.04	37.80		
	Bwssb cutting along road		1	300.00	0.80	0.04	9.60		
						Total Qty	**85.24**	**9901.17**	**843975.73**
13	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface - Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sq.m. area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC :35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. (Page No,-181, I.No.-24.15 of KPWD S.R 2015-16).								
	Edge Lane	Sqm	2	346.00	0.10		69.20		
						Total Qty	**69.20**	**473.04**	**32734.37**
14							**Total construction cost**		**14,63,548.15**
15							**Design Report,Quality Control Checking & PMC Amount**		**29,270.96**
16							**Sub Total**		**14,92,819.11**
							Mescellaneous and Rounding off		**7,180.89**
							Grand Total		**15,00,000.00**

Certificate:
1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2015-16
4. The provisions made in the estimate are necessary and essential.

Consultant
For Sri Sai Consultants

Assistant Engineer
Ward No-15
BBMP Bangalore

Assistant Executive Engineer
Dasarahalli-Sub division
BBMP Bangalore

Executive Engineer
Dasarahalli
BBMP Bangalore

Sl No	Description of Work	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
8	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per directions of the Engineer-in-charge. Specification No. KBS 4.6.3(Item no: 4.46.2, Page no: 17 of KPWD S.R 2015-16).								
	Chapalamma Circle Road								
	CH:00-256	T	1	3.69			3.69		
						Total Qty	3.69	69805.80	2,57,845.17
9	KSRRB M600-2. Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 25mm and down size graded granite metal coarse aggregate with superplastisizer at 3lts conforming to IS 9103-1999 reaffirmed 2008, (Coarse and fine aggregate conforming to IS: 383) mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver,spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane,sealant primer, joint sealant, debonding strip, dowel bar, tie rod, ,admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications MORTH Specification No. 602- with M30 @ 360 Kg/cum Cement, C.A, 0.69 cum F.A. 0.46 cum.(Page No.-173 I.No-22.2.1 of KPWD S.R 2015-16).								
	Sharadha School 1st and 2nd Cross Road								
	Ch:00-50		2	50.00	3.50	0.15	52.50		
	MTS Colony Road						0.00		
	Ch:00-60	Cum	1	60.00	3.30	0.15	29.70		
	Chapalamma Circle Road						0.00		
	Ch:00-33		1	33.00	3.50	0.15	17.33		
	Ch:33-73		1	40.00	5.00	0.15	30.00		
	Ch:73-100		1	27.00	4.50	0.15	18.23		
						Total Qty	147.75	6943.32	1025875.53
10								Total Constrution cost	19,41,704.12
11								Design Report,Proof Checking & PMC Amount	48,542.60
12								Sub Total	19,90,246.72
13								Miscellaneous & Rounding Off	9,753.28
								Grand Total	20,00,000.00

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2015-16
4. The provisions made in the estimate are necessary and essential.

SRI SAI CONSULTANTS BANGALORE-90

Consultants
For Sri Sai Consultants

ನಂ. EE/DD/RS/86/2015-16 ದಿನಾಂಕ : 25.1.16
ರೂ. 20.00 ಲಕ್ಷ ರೂಪಾಯಿ (ರೂ. ಇಪ್ಪತ್ತು ಲಕ್ಷ ರೂಪಾಯಿ ಮಾತ್ರ)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
P-18
86

Assistant Engineer
Ward No-15
BBMP - Bangalore

Assistant Executive Engineer
Dasrahalli-Sub division
BBMP - Bangalore

Executive Engineer
Dasrahalli
BBMP - Bangalore

ನಂ. CE/DZ/AS/ /15-16 ದಿನಾಂಕ : 25.1.16
ರೂ. 20,00,000/- (ಇಪ್ಪತ್ತು ಲಕ್ಷ ರೂಪಾಯಿಗಳಿಗೆ)
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬ
ದಾಸರಹಳ್ಳಿ